BRUHATH BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

SCHEDULE-B

Tender Notification No:BBMP/DZ/ EE(Ele)/TN/02/2016-17 Date: 2.07.2016

Name of the Work: Operation and Maintenance of street lights at Ward No-12, Shettihalli (Shettahalli Surrounding Area), Package-D1 of Dasarahalli Zone.

Sl No	Description Of Work	Unit	Approved Qty	Rates Quted By contractor	
				Rates In Figure	Amount In Words
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starter ,Drawing of suitable capacity double insulated wire along with messenger wire in place of damaged LTUG cable of street lighting system and Painting of street light & park MS tubualar Poles and footing, Pole numbering ,switching ON/OFF of street lights at specified timing and Preparing data bank of street lights, TC wise & Circuit Wise Master register for each ward, removing of buntings Posters, threads, banners from the street light poles and carrying out routine maintenance, cleaning of perfex covers, pruning of trees around fittings periodically, furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below.				
2	i) Supply and replacing of 36/40 W fluorescent tube light accessories complete like luminaries, lamps, control gear,wire etc .,	Each	120	108	Rupees One Hundred and Eight Only
3	ii) Supply and replacing of 125 HPMV fitting accessories complete like lamps, control gear, wire etc.,	Each	26	9	Rupees Nine Only
4	iii) Supply and replacing of 250W HPSV fitting accessories complete like lamps, control gear,wire etc.,	Each	2033	900	Rupees Nine Hundred Only
5	iv) Supply & Replacing of 400 watts HPMH fitting accessories complete like chokes,igniter, lamps, control gear,control ropes,internal mast cable,etc complete for High mast lighting system.	Each	108	900	Rupees Nine Hundred Only
6	Operation and maintenance of Manual and Automatic Timer Switching circuits including replacement of electrical gadgets, such as MCB's Contactors, Timer, Cut outs, wiring connector and M.S. Box with proper insulation etc., complete.	Each	90	10	Rupees Ten Only
7	Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole. a) Upto 5Mtr street light pole.	Each	26	5	Rupees Five Only
8	b) 8 Mtr and above street light pole.	Each	50	9	Rupees Nine Only

I am Prepared to Take Up the above Work at The Rates Mentioned In The Schedule-B

For VIJAYALAKSHMI ASSOCIATES

Sing Of the contracter
Proprietor

29/11/17

Executive Engineer(Ele)
Bruhat Bangalore Maha Nagara Palike
Dasarahalli zone

Executive Engineer (Ele)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned by CamScanner